
Contents

1	General Description	1
	Introduction	1
	General Organization of a Sodium-Cooled Fast Reactor	1
	Superphenix Specific Case	2
	The Fuel Sub-assembly	2
	The Core	4
	The Reactor Block	6
	The Primary Circuit	8
	The Secondary Loops and the Electricity Generation	10
	The Auxiliary Circuits	13
	The Handling	13
	The Instrumentation and Control and Electrical	
	Power Supply	16
	The Buildings	18
	Operating Mode	19
	References	21
2	Construction Review	23
	A European Reactor	23
	General Organization	23
	Construction Site Beginning Date	24
	Industrial Organization	24
	The Overall Progress of the Reactor Block	
	Construction Site	26
	The Fabrications in On-site Workshop for Large	
	Diameter Structures	26
	Other Manufacturing and Exceptional Transports	26
	The Civil Engineering	27
	Reactor Block	27
	On-site Workshop	28
	The Manufacturing in the On-site Workshop	28
	The Notion of Package	28
	Manufacturing and Storage Methods	29
	The Package Transfer and Assembly in the Reactor Block	30
	First Package: The Safety Vessel (260 t)	30

Second Package: The Main Vessel + The Core Catcher + The B1 Baffle (700 t)	30
Third Package: Conical and Toroidal Inner Vessels + Baffles + Chimneys + Pump Skirts (560 t)	31
Fourth Package: The Reactor Slab	31
Main Vessel/Slab Welding	32
Welding Safety Vessel/Slab	32
Setting-up the Dead Body	33
Setting-up the Dome Cylindrical Body	33
Setting-up the Diagrid	33
Setting-up the Rotating Plugs	33
Setting-up the Dome (400 t)	33
Setting-up the Storage Drum	34
Works Finalization	34
Works in the Plant “Conventional” Part	34
The Schedule	35
The Costs	36
The Construction Costs	36
Benchmarking with Water Reactors	38
The Other Construction Sites	38
Conclusion and Recommendations	39
References	40
3 Start-up Trials	41
General Organization of Start-up Trials	41
Phase 1: Subset Testing	41
Phase 2: Filling-in with Sodium	42
Phase 3: In-Sodium Isothermal Trials	42
Phase 4: Rise to Rated Power	42
Phase 1 Trials	42
Progress	42
Phase 1 Trial Results	43
Phase 2 Trials	43
Progress	43
Phase 2 Trial Results	44
Phase 3 Trials	45
Progress	45
Phase 3 Trial Results	45
Phase 4 Trials	45
Progress	45
Phase 4 Trial Results	46
Internal Structure Vibrations	47
Reminders	47
Vibrations Observed on the Reactor	47
Analysis	47
Solving the Problem	48
Application to the Reactor and Consequence Analysis	48

Partial Load Operations	49
Conclusion	49
Hydraulic and Thermal Hydraulic Trials	49
Hydraulic Trials	49
Thermal-Hydraulic Trials	49
Conclusion and Recommendations	50
Reference	50
4 Objectives and Operation Results	51
Introduction	52
Superphenix Reactor Initial Objective.	52
The First Problems.	52
Situation in December 1986	53
Operation/Shutdown Period Chronology	53
First Operating Phase Untill the Storage Drum Leak	53
Phase 2: 83-EFPD Outage for Modifications	
Following the Storage Drum Unavailability	54
Phase 3: Second Production Period Untill	
the 160-EFPD Outage	54
Phase 4: Outage Period Until March 27, 1990	54
Phase 5: Third Production Period from April	
to July 1990, Ended by the Air Ingress Incident	54
Phase 6: Reactor Outage for Sodium Purification	
and Various Consequences up to 1994.	55
Phase 7: Re-start and Third Production Period	55
Phase 8: Outage so as to Repair an Intermediate	
Heat Exchanger Seal Argon Supply	56
Phase 9: Fourth and Final Production Period.	56
Phase 10: Definitive Shutdown	56
Operation Review Results.	56
Objective Drift and Support Erosion.	57
Phenix and Superphenix: Technical Problem Comparison	58
Conclusion	59
References	60
5 Safety	61
The Safety Principles Applied During Initial Design	61
Introduction	61
Reactivity Control	62
The Residual Power Removal	63
Radioactive Product Containment	64
Sodium-Related Protections	66
The Containment Design Basis Accident (ADC)	67
Conclusion	68
Reactor Safety Review	68
Safety During Operations	70
Additional Procedures	70

The State-Oriented Approach (APE)	71
Probabilistic Safety Assessment (PSA)	71
The Safety Requirement Evolutions During the Operating Period	71
Spray Sodium Fires	72
Gas Passing Through the Core	72
Entire or Local Core Meltdown Scenarios (ULOF/BTI/RIB).	72
Energy Released by a Sodium/Molten Core Interaction	74
Making Reliable the Steam Generator Depressurization	75
Sodium Aerosol Releases	75
In-Service Inspection	75
Conclusion	76
Conclusions and Recommendations	76
References	77
6 Operating Experience	79
Introduction	79
Unavailability Review	79
Attempt to Compare a PWR and Superphenix Operations.	81
Introduction	81
Reactor Control.	81
The Core and the Fuel	82
The Safety	82
The Circuits	83
The Fuel Handling	84
Maintenance and Inspection	84
Miscellaneous Points	85
Conclusion and Recommendations	85
7 Fuel Sub-assembly	87
Introduction	87
General Description	88
Design Parameters	88
Phenix Experience Feedback	88
Detailed Description and Features	89
The Upper Neutron Shielding	89
The Hexagonal Tube	89
The Pins	89
The Pellets	89
Sub-assembly Foot	90
Connections Between Diagrid and Sub-assemblies, with Controlled Leaks	90
Summary of the Main Features	90
Manufacturing	90
History.	90
Pellet Fabrication	91
Sub-assembly Manufacturing	92
Manufacturing Cost	93
Conclusion	93

Special Manufacturing	93
Plutonium Isotopy	93
Superphenix Fuel Validation Tests	93
Operating Experience Feedback	95
Grid Follow-up	95
Conclusions and Recommendations for the Future	95
References	96
8 Neutronics	97
Introduction	97
Description of the Core	98
Core Composition	98
Enrichment Zones	98
Management Mode	98
Void Effect.	99
Core Monitoring and Control	99
Neutron Monitoring.	99
Thermal Monitoring.	99
Clad Failure Detection and Location	100
Flow Rate and Core Inlet Temperature Measurements	100
“Scientific” Measurements	100
Difficulties and Experience Feedback.	101
Loading the Core and Divergence	101
The Trial Results from Start-up to Nominal Power.	103
Introduction	103
Control Rod Negative Reactivity Value	103
Feedback Coefficients	103
Power and Flux Distribution	104
Hydraulics and Thermo-hydraulics.	104
Control Rod Position	104
Conclusions	105
Core Follow-up During Reactor Operations.	105
Core Follow-up Methodology	105
Zero-Power Trials	105
In-Operations Monitoring	106
Operating Experience	110
General Experience	110
Major Measurement Campaigns During Operations	110
Conclusion	110
Conclusions and Recommendations for the Future	111
References	112
9 The Primary Pumps.	113
Superphenix Primary Pump Features	113
Functions	113
General Description	114
Main Dimensional Features	114
Operating Conditions	115
Instrumentation	115

Inertia and Rotation Speed	115
Hydrostatic Bearing Design.	116
In-Sodium Hydraulic Stream and Cavitation	116
Shutter	117
Shaft Line Sizing and Realization	118
Taking-Over Expansions Between Slab and Junction with the Diagrid	118
The Pump/Diagrid Link (LIPOSO) Tightness	119
Promising Tracks that Did not Come to an End.	121
Ferrofluid Packing Boxes	121
The Supercritical Shaft.	122
The Instrumentation	122
The Materials	123
Phenix Experience Feedback Integration	124
Manufacturing	124
In-Water Tests.	125
In-Reactor Operations.	126
Post Mortem Analyses	127
Conclusions	127
Proposals for the Future	127
References	128
10 Secondary Pumps and Circuits	129
The Secondary Pump	129
General Functions	129
Pump Design Issues.	129
In-Water Tests at Gennevilliers	130
Secondary Pump Description	130
Secondary Pump Main Features	130
Materials	131
The Expansion Tank	131
Expansion Tank Description	131
Instrumentation	132
Operating Experience Feedback.	132
Materials and Post-mortem Analysis	132
The Sodium/Air Heat Exchanger	132
Function.	132
Design	132
Description.	133
Instrumentation	133
Materials	133
Main Features.	133
Operating Experience.	134
Isometry and Overall Organization of the Loop	134
Piping and Overall Isometry	134
Natural Convection Operations	134
Experience Feedback	135
Conclusion and Recommendations for the Future.	135

11 Intermediate Heat Exchangers	137
Functions	137
Description	138
Characteristics and Operating Conditions	138
Instrumentation	139
Design Issues	139
Phenix Experience Feedback on the Secondary	
Outlet Collector.	139
Seismic Resistance	140
Thermosiphons	140
Manufacturing and Controls	140
Connections of Exchange Tubes to the Tube Plates	140
Device to Soften the Collector Inner Shell	140
Non accessible Welds	141
Overall Control	141
The Materials	141
Test Review Before Introduction in Reactor	142
Operating Experience	142
Leak on the Exchanger Argon Seal	143
Post-mortem Analyses	144
Conclusions	145
Recommendations for the Future	145
References	146
 12 The Steam Generators	 147
Steam Generator Function.	147
Design Issues/Phenix Experience Feedback	147
General Description	148
Envelope	148
Support Structure	148
Sodium Circulation	149
Tube Bundle/Support Structure	149
The Tube Bundle	150
Main Features	151
Instrumentation	151
Thermodynamics.	151
Level Measurements	151
Sodium/Water Reaction Detection	151
Sodium/Water Reaction	152
Materials	152
Adjustment and Qualification Tests	153
Hydraulic Mockups	153
Hydro-Elastic Mockups	153
Mechanical and Thermo-mechanical Mockups.	153
Overall Mockups.	153
Conclusion on Tests	153
Manufacturing and Control	154
Tubes	154
Outer Envelope	154

Operating Experience	154
Duration.	154
Start-up Test Results	155
Transient Book Keeping and Monitoring	155
Incidents	155
Hydraulic Re-test	155
Water Chemistry	155
Conclusions	156
Recommendations for the Future	156
References	157
13 The Sodium/Water Reactions	159
Reminders on Sodium/Water Reactions	159
Knowledge of Wastage Mechanisms	161
Prevention of Sodium/Water Reactions.	162
Manufacturing.	162
Choice of Materials	163
Design	163
Detection	164
Hydrogen Detection: Coexistence of in-Sodium and in-Argon Measurements	164
Description of the BDH in-Sodium Hydrogen Detection System	164
BDH Performances	164
BDH Calibration	165
BDD Detection	165
Acoustic Detection (DA)	166
Conclusion	166
Mitigation.	167
Repair and Re-start	167
Location of the Leak	167
Identification of Weakened Tubes	168
Repair Procedure.	168
Secondary Loop Reconditioning	168
Conclusion	169
Conclusions and Recommendations for the Future	169
References	170
14 Sodium Leaks and Fires	171
Reminders on Sodium Fires	171
Prevention	173
Phenix Experience Feedback.	173
The Provisions Taken at Superphenix	173
The Experience Feedback.	174
Conclusion	174
Detection	174
The Instrumentation.	174
The Under-Thermal-Insulation Leakage Issue	176
The Spurious Alarm Issue	177

Level Measurements	177
The Staff	177
The Experience Feedback on Leaks, Which Occurred	177
Conclusions	177
Mitigation	178
Circuit Draining	178
Choosing a Sizing Leak	178
The Sodium Aerosol Release Issues in Accidental Situations	179
The 1992–1994 Worksite	180
Conclusions and Recommendations for the Future	182
References	183
15 Reactor Shutdown and Control Systems	185
Introduction	185
Phenix Experience Feedback	186
Description of Superphenix Control Rods	186
General Architecture	186
Description of the Control Sub-assembly (Rod and Sheath)	187
Absorbent Element Description	187
Description of Rod Mechanisms	188
The Back-up Shutdown System	189
Validation Tests	189
RBC Mechanisms	190
Back-up Shutdown System	190
Instrumentation and Control	190
Operations with Power Setting	190
Reactivity Control	191
B ₄ C Melting of a SAC Rod Issue During House Load Operation or Automatic Power Fallback Transients	192
Experience Feedback	192
Reliability	192
Rod Worth	192
SAC Spurious Falls	193
RPRa and RPRB Experience Feedback	193
House Load Operations or Automatic Power Fallback	193
Improvements Brought up During Operations	193
Lifetime	194
Absorbent Dismantling	194
Conclusions and Recommendations	194
Reference	195
16 Decay Heat Removal	197
Introduction	198
Reminders on the Decay Heat Removal Issues	198
From Phenix to Superphenix: Design Evolutions	198
Brief Description of Evacuation Circuits	199
BPR	199

RUR	199
RUS	200
Residual Power Measurement Trials at Superphenix	200
Superphenix Decay Heat Removal Modes	202
Removal Tests in Generalized Natural Convection	203
Experience Feedback of RUR Residual Power Removal Circuits	205
Conclusion and Recommendations for the Future	205
References	206
17 The Materials	207
Reminders of the Material Operating Condition Specificities in a Sodium Fast Reactor	208
Reminders of the Importance of the Manufacturing and Realization Quality	208
Rapsodie/Phenix Experience Feedback and Related Choices for Superphenix Materials	209
The Choices of Materials for Superphenix Structures and Components	210
316L	210
316 SPH	210
304 L	211
304 H	211
800SPX Alloy	211
15D3	212
A 42/A 48	213
10 CD 9-10 Low Alloy Steel	213
CF3	213
X20T3	214
Fuel Sub-assembly Materials	214
Fuel Cladding	214
Hexagonal Tubes	214
Conclusion on the Material Choices	214
The Coatings	215
Austenitic Steel Welding	215
The Storage Drum Leak (See Chap. 22 “The Handling”)	215
Other Operating Experiences	217
Fatigue Cracking	217
Stress Caustic Corrosion Cracking	217
Risk of Corrosion in the Drawdown Zone	217
Extended Operation with High Oxygen Content	218
Clad Failures	218
Quality of Castings	218
Conclusion	218
«Post Mortem» Analysis Program	218
The New Materials	218
The Most “Loaded” Zones	218
The Primary Pumps	218
The Intermediate Heat Exchangers	219

Sodium/Air Heat Exchangers of the Residual Power Removal Circuits (RUR)	219
Steam Generators	219
Secondary Loops.	219
Conclusions and Recommendations for the Future	219
References	220
18 Hydraulics and Thermo-hydraulics	221
General Problems Posed by Thermo-hydraulics on Sodium	
Fast Neutron Reactors	222
The Simulation Tools.	222
Introduction	222
Water or Sodium?	222
Hydraulics	223
Stratification	224
Gas Entrainment via Flows.	224
Conclusion	224
The Reactor Block Sodium Thermo-hydraulics	224
The Cold Pool	224
The Hot Pool	225
Conclusions	228
The Reactor Block Gas Thermo-hydraulics	228
Introduction	228
Thermosiphons in Component Penetrations.	229
Heat Insulation in the Main Vessel On-Hold-Piece Zone	229
Metallic Heat Insulation Between Main and Safety	
Vessels in On-Hold-Piece Zone.	229
Slab On-Hold-Piece Cooling Circuit	229
Sodium Deposits	229
Temperature Asymmetries on the Main Vessel	
In-Gas Part.	230
Conclusion	230
The Components	230
The Natural Convection	230
Natural Convection on Primary Side	230
Natural Convection on Secondary Side	231
Conclusion	231
Gas Being Entrained by Sodium	231
Argon Being Entrained in Nominal Conditions	231
Phenix Negative Reactivity Scrams	
and the Consequences for Superphenix	232
Conclusions and Recommendations for the Future	233
References	234
19 In-Service Inspection	235
Introduction	235
Definition of the Major In-Service Inspections.	236
Main Vessel	236
Safety Vessel	237

Slab.	237
Core Support Plate	237
Diagrid and Diagrid Support.	237
LIPOSO (Pump-Diagrid Link)	238
Internal Vessels.	238
BCC (Core Cover Plug).	238
Rotating Plugs	238
Components	238
Studied Solutions but that Remained at a Study State	238
Conclusion	239
Experience Feedback of the Major In-Service Inspections	
Carried Out During the Reactor Life	239
Inspection of Superphenix Vessels.	239
Triple Point Control.	241
Core Cover Visual Inspection	242
Controlling the Position of the Core Support Structure.	243
Studies so as to Know the Reactor Upper	
Closure Sealing.	243
Ultrasonic Testing of Steam Generator Tubes	243
Steam Generator Hydraulic Tests.	246
Miscellaneous	247
Conclusion	247
Transient Book Keeping and Monitoring	247
Manufacturing Quality Review	249
Conclusions and Recommendations for the Future	249
References	250
20 The Chemistry	251
Consequences of the Sodium Chemical Properties	252
Application of Phenix Experience Feedback	252
Superphenix Sodium Monitoring and Control Systems	253
The Plugging Indicators	253
The Purification System (Cold Trap)	255
The Hydrogen Detections.	256
TASTENA Sampling	256
The Start-up External Purification Unit	256
Filling-in the Reactor and Start-up Purification	257
Primary and Secondary Sodium Activation	258
Primary Circuit Pollution Incident	259
Incident Progress.	259
Purification Campaigns	259
Incident Consequences.	259
Lessons and Corrective Actions.	260
Cold Trap Operating Experience and Developments.	261
Driving Rules	261
Cold Trap Infilling Follow-up.	261
Cold Trap or Cartridge Lifetime Before Plugging	262
In-Operations Feedback	262
Review of Used Cartridges.	263

Trapping Tritium	263
Corrosion and Mass Transfers	264
Corrosion	264
Activation of Corrosion Products.	265
Quantifying Corrosion and Deposits	265
Sub-assembly Dripping-Washing	265
The Water Chemistry	266
Conclusion and Recomendations	266
References	268
21 The Sodium Technology	271
Introduction	271
Reminder of Some Sodium Properties	272
A Metallic Fluid	272
Austenitic Steel Difficult Tribology	272
A Solidification Below 98 °C	272
Tendencies to Thermal Stripping.	272
Sodium Valves	272
Precautions of Use.	274
Experience Feedback	274
Conclusion	275
Electromagnetic Pumps.	275
Precautions of Use.	275
Experience Feedback	275
Conclusion	276
Measurement Instrumentation	276
Temperature	276
Level Measurements	276
Pressure Measurements	276
Flow Rate Measurements	277
Miscellaneous	277
Sodium Circuits.	278
Thermal Stripping and Mixers.	278
Piping Support Structures	278
Storage Tanks.	278
Argon Circuits.	279
Equipment Using NaK	279
Wetting and Tribology	280
Mechanical Problems Occurred on the Clad Failure	
Detection and Location Modules (RGS and RGR)	281
Conclusions and Recommendations	281
Reference	282
22 The Handling.	283
General Description of Superphenix Initial Handling System.	284
Phenix Experience Feedback.	284
Circuit Functions.	284
Operating Conditions	284
Fresh Sub-assembly Pathway	285

Irradiated Sub-assembly Pathway.	286
Brief Description of the In-Sodium Handling Chain Main	
Components (Primary Handling)	287
Rotating Transfer Lock and Inclined Ramps	287
Transfer Machines	287
Storage Drum	288
Operating Experience Feedback with Storage Drum	
Available	289
Operating Results	289
Encountered Difficulties	290
Conclusion	291
Incident of the Storage Drum Leak and Change	
of the Handling Chain	291
The Incident Progress	291
Switching to an in-Gas Handling.	292
Transfer Time Maximum Durations	292
Other Consequences	293
The In-Gas Handling Campaign Experience Feedback	293
The Context	293
The Optimization of the Core Sub-assembly	
and Element Washing	293
The Campaign Progress	294
Encountered Difficulties	294
Conclusion on the Rates.	295
Special Handlings	296
Principle and Description	296
Operations Mode.	296
Experience Feedback	297
Conclusions and Recommendations for the Future	298
References	299
23 The Environmental Results.	301
Introduction	301
Reminder of the Contamination Sources	302
Fuel.	302
Sodium Activation.	302
Activation of Impurities Contained in the Sodium	302
Structure Activation.	303
Activation Products Present in the Core Cover Gas	303
The Gaseous Releases	303
The Case of Tritium.	304
Source Calculation.	304
Tritium Behaviour in the Circuits	304
Measurements.	304
Estimates After Shutdown	305
Estimates of Tritium Releases During “Washing”	305
The Liquid Waste	306
Irradiated Sub-assembly Washing	306
Component Washing	306

The Solid Waste	306
Conventional Waste.	307
Radioactive Waste.	307
Chemical Releases	307
The Thermal Releases	308
The Dosimetry	308
Conclusion and Recommendations.	308
References	310
24 The Dismantling.	311
Introduction	311
International Experience for Sodium-Cooled Fast Reactor	
Dismantling	311
US Reactors: EBR1, EBR2, EFFBR (FERMI-1), FFTF	312
United Kingdom Reactors: PFR and DFR	312
The Soviet-Designed Reactors: BOR 10 and BN350	312
KNK II German Reactor	313
The French Reactor Rapsodie	313
Conclusion	314
Superphenix Operation Progress	314
Phase 1	314
Phase 2	315
Phase 3	316
Phase 4	316
Phase 5	316
Phase 6	317
Phase 7	318
A Fast Reactor Dismantling General Specificities.	318
Sub-assembly Washing	318
Keeping Sodium Under Liquid Form.	318
Getting Out Removable Components	318
Provisions for Cold Traps Containing Active Products.	318
Sodium Processing	319
Processing of All the Circuits Having Contained Sodium . . .	319
NaK Processing	320
Reminder of the Difficulties and Necessary Developments	320
Sodium Residual Volumes in the Reactor Block	320
Control Rods	320
Cold Traps	321
Activity Level.	321
Tritium	321
MESOS	321
Dismantling Environmental Impacts.	322
Recommendations for the Design of Future Reactors	322
Materials	322
Accessibility to PNL (Lateral Neutron Shielding)	322
Reactor Block Draining Capacity	322
Minimization of Aerosol Deposits	322
Avoid the Use of NaK.	322

Waste Zoning	323
Tritium	323
Primary Cold Traps	323
Various Cold Trap or Their Cartridge Processing	323
Control Rods	323
References	323
25 Superphenix Children	325
Introduction	325
Reminder of the Major Design Changes Between Phenix and Superphenix	326
Design Evolution from Superphenix to SPX2	327
Introduction	327
Core and Sub-assemblies	327
The Reactor Block	328
The Large Components	329
The Fuel Handling	331
Conclusion/Weight and Cost Savings.	331
From SPX2 to EFR	332
Introduction	332
External Contributions from Partners	332
Optimizing the Number of Loops	332
The Core	332
The Reactor Block	332
Residual Power Removal	334
The Reactor Building.	334
Conclusion and Results	334
The Safety Evolution from Superphenix to EFR	334
Conclusion and Recommendations	336
References	337
26 Conclusion.	339
An Almost Unlimited Energy for the Planet with SFR Technology	339
Interesting Environmental Results	340
A Minimization of Final Waste in Quantity and Dangerousness	340
Real Scientific Achievements for the Future	340
An Opening on the Future	341
A Permanent Challenge	341
Reference	342

Superphenix

Technical and Scientific Achievements

Guidez, J.; Prêle, G.

2017, XL, 342 p. 342 illus., 283 illus. in color.,

Hardcover

ISBN: 978-94-6239-245-8

A product of Atlantis Press